



# Meadowstone

TECHNICAL DATA SHEET

TDS/006 FEBRUARY 2010

the cast stone people

## STANDARD PORTICO DETAILS

### Stage 1—Columns

Construct column as shown in Technical Data Sheet TDS/002.

### Stage 2—Steel Support

Place support steel onto columns, bolt or build in ends to wall.

### Stage 3—Architrave

Set up timber to support 'L' architrave, lay and line stone dry. Screw threaded rods into cast-in sockets and tighten both nuts over washers. Drill 2 holes into vertical leg of architrave and insert capped dowels. Fill and point perp joints.

### Stage 4—Cornice

Bed cornice onto top plate, insert bolts (2 per stone). Do not over tighten bolts.

### Stage 5—Coping

Lay DPC on cornice and bed coping including fixing dowels.

